

DAV PUBLIC SCHOOL

MEERACHAK, INDUSTRIAL ESTATE, BARARI, BHAGALPUR, BIHAR - 812003 Affiliated to CBSE, Delhi, Upto Senior Secondary Level, Affiliation No.: 330127

Ref. No .:- DAV/BGP/ 2024/.32/

Date: 22.106.1202.4

कार्यालय डी.ए.वी. पब्लिक स्कूल, बरारी, भागलपुर

डी.ए.वी. पब्लिक स्कूल, बरारी, भागलपुर में चारदिवारी को दो फीट ऊँचा करके, उसके ऊपर कँटीले तार से तार बन्दी के लिए योजनाओं और अनुमानों का अनुमोदन, संबंधित फॉर्म संस्थान, आपूर्तिकर्त्ता अपनी लागत क्षमता निर्माण सामग्री के साथ का ब्यौरा देते हुए, निविदा की शत्तों पर सहमति पत्र प्रेषित करते हुए अधोहस्ताक्षरी के कार्यालय में एक सप्ताह के अंदर (दिनांक 20/06/2024 से 30/06/2024) तक कार्यालय अवधि (09:00 A.M. to 02:00 PM) तक निविदा फार्म भरकर जमा कर सकते हैं। विस्तृत विवरण School के Website पर उपलब्ध है।

(अनिल कुमार)
प्राचार्य
डी.ए.वी. पब्लिक स्कूल,
बरारी भागलपुर
Principal
DAV Public School
Meerachak Industrial Estate
Barari, Bhagalpur
Affiliation. No. 330127
School Code 65129

D.A.V. PUBLIC SCHOOL, MEERA CHAK, INDUSTRIAL ESTATE, BARARI, BHAGALPUR, BIHAR.

MOB:-9939542745, E-MAIL:-bgpdav@gmail.com

REF:-DAV-BBP/SB/ACW/BOQ/01/24-25

Date: - 24 JUNE. 2024

BILL OF QUANTITIES

BH	HAGALPUR, I	BIHAR.				
.No.	S.O.R.	DESCRIPTION	Qty.	Unit.	Rate	Amount
		(A) Addition on Compound wall - Length= 1770'-9", Addition				
		Area of construction of addition of Compound wall = 1	770'-9"x2'-0"	= 3541.	5 SFT(329	9.14 SM)
		SECTION- I (DEMOLITION WORK)				
1	15.3	Demolishing R.C.C. work including stacking of steel				
		bars and disposal of unserviceable material within 50				
		metres lead.	3.12	Cum		
		SECTION-II (P.C.C./R.C.C. WORK)				
2	5.2	Reinforced cement concrete work in wall(any			4.17	
		thickness) including attach pilasters, buttresses,				
		plinth and string courses, fillets, columns, pillars,				
		piers, abutments, posts and struts etc. upto floor five				
		level excluding cost of centering, shuttering			30	
		finishing and reinforcement.				
	5.2.2	1:1.5:3 (1 cement; 1.5 coarse sand; 3 graded stone		-		
		aggregate 20mm nominal size.)	9.37	Cum		
3	5.3	Reinforced cement concrete work in beams, suspen-				
		ded floors, roofs having slope up to 15, landings,				
		balconies, shelves, chajjas, lintels, bands, plain				
		window sills, staircases and spiral stair cases up to				
		floor five level excluding the cost of centring, shutte-		1		ALL THE
		ring , finishing and reinforcement with 1:1.5:3 (1				
		cement :1.5 coarse sand: 3 graded stone aggregate				
		20mm nominal size).	10.41	Cum		
4	5.9	Centering and shuttering including strutting				
		propping etc and removal of form for				
	5.9.5	Lintels, beams, plinth beams, girders, bressumers				
		and cantilevers.	82.28	Sqm		
	5.9.6	Columns, pillars, piers, abutments posts and struts.	148.55			
5		Reinforcement for R.C.C. work including straight-				
		ening ,cutting ,bending,placing in position and				
		binding all complete.				
	5.22.1B	Mild steel - 6mm dia.	475	Kg		
	5.22.7A	Thermo-Mechanically treated bars TMTC-500-	450			
		8mm dia.				
	5.22.7C	Thermo-Mechanically treated bars TMTC-500-	548	Kg		
		12 mm dia.				
		SECTION-III (BRICK WORK)				

Cum Asstt, Regional Officer DAV Public School Meerachak Industrial Estate Barari, Bhagalpur Affiliation. No.-330127

SI.No.	S.O.R.	DESCRIPTION	Qty.	Unit.	Rate	Amount
6	6.1A+	Brick work with bricks of class designation 100A in				
	6.1.14A+	superstructure above plinth level upto floor V level				
	6.3A	in Cement mortar 1:6(1 cement; 6 coarse sand)	67.42	Cum		
		SECTION-IV (PLASTER WORK)				
7	13.11	12mm cement plaster of mix:				
	13.11.4	1:6 (1 cement; 6 coarse sand).	411.42	Sqm		
8	13.12.	15 mm cement plaster on rough side of single or				
		half brick wall of mix.			RATE.	
	13.12.4	1:6 (1 cement; 6 coarse sand).	548.00	Sqm		
		SECTION-V (FINISHING WORK)				
9	13.46A	Finishing walls with premium Acrylic Smooth exterior				
		paint with silicone additives of required shade:				
	13.46A.1	New work(Two or more coat applied @ 1.43 ltr/10				
		sqm over and including priming coat of exterior	959.42	Sqm		
		primer applied @ 2.20 kg/10 sqm)				
		TOTAL				
		ROUNDUP		A I		
		Cost of construction per sq.ft.				

Principal Cum Asstt. Regional Officer
DAV Public School
Meerachak Industrial Estate
Barari, Bhagalpur
Affiliation. No.-330127